

REQUEST FOR HEARING

PLANNING COMMISSION: OAK HILL, TENNESSEE

Date Submitted: 08/10/22 PC Meeting Date: 10/04/22

The undersigned hereby requests consideration for a decision of the Planning Commission of Oak Hill, Tennessee, wherein Baird Graham
Owner/Developer/Architect/Engineer
of the property located at: 1167 Travelers Ridge Drive Nashville, TN 37220

Lot Number(s): 39 Subdivision: Inns of Granny White

The property is in Zoning District _____, in accordance with plans, application, and all data filed with the City of Oak Hill.

Radnor Lake Natural Area Impact Zone

Y

or

N

Steep Slope

Y

or

N

Plat/Subdivision

Y

or

N

Project Explanation: Building New Single family Home


Planning Commission Meeting Date: 10/04/22

Baird Graham
Applicant Name (Name)

921 Robertson Academy Road Nashville, TN 37220
Applicant Address

615-804-7008
Applicant Phone Number

baird@bgc-construction.com
Applicant Email Address


Applicant (Signature)

City of Oak Hill (Signature)

Parcel No. _____

Case No. _____

Fee Amount: \$ 1250.00

SITE - GRADING PLANS

NEW RESIDENCE

1167 TRAVELERS RIDGE DRIVE CITY of OAK HILL

Nashville-Davidson County, Tennessee 34th Councilmanic District

Civil Engineer
 Tony Snyder
 Snyder Engineering pllc
 228 Spence Lane
 Nashville, Tennessee 37210
 615-383-1699
 tonysnyder@comcast.net

Surveyor
 Campbell McRae & Associates Inc.
 P.O.Box 41153
 Nashville, Tennessee 37204
 Phone 615-298-2424 cmas@att.net

Architect
 Zinc Architecture
 5820 Fredricksburg Drive
 Nashville, Tennessee 37215
 www.zincarch.com

UTILITIES

Electric Service
 Nashville Electric Service
 1214 Church St.
 Nashville, Tennessee 37246
 Joe Valleley 615-747-3261

Water Service
 Metro Water Service
 1600 2nd Ave. N
 Nashville, Tennessee 37208
 Christian Thompson -615-862-7229


Sewer Service
 Metro Water Service
 1600 2nd Ave. N
 Nashville, Tennessee 37208
 615-862-4598

Gas Service
 Piedmont Natural Gas
 800-752-7504

Tennessee One Call 800-351-1111


Sheet Index

- | | |
|---|------------------------|
| 1 | TITLE |
| 2 | EXISTING CONDITIONS |
| 3 | SITE PLAN |
| 4 | GRADING & UTILITY PLAN |
| 5 | RAIN GARDEN PLAN |
| 6 | EROSION CONTROL PLAN |
| 7 | DISTURBED AREA |
| 8 | TREE PLAN |
| 9 | DETAILS |



Location Map
(NTS)


Snyder Engineering, pllc
 CIVIL ENGINEERING SERVICES
 Phone 615-383-1699
 228 Spence Lane
 Nashville, TN 37210 tonysnyder@comcast.net



TITLE SHEET
 New Residence
 1167 Travelers Ridge Drive
 Nashville, Tennessee 37220
 Map 145 Parcel 073

DR.	CHK.	DATE	DESCRIPTION

FILE NO. 1113-21



RESUBDIVISION OF LOTS
34 & 35,
INNS OF GRANNY WHITE
BOOK 6900, PAGE 412
R.O.D.C., TN

35
IOANNIDES,
SOCRATES A.
INSTRUMENT#
20040223-0020115
R.O.D.C., TN.
PARCEL ID
14507006900
P.A.D.C., TN

36
WILLIAMSON FAMILY
REVOCABLE LIVING TRUST
INSTRUMENT#
20150901-0088439
R.O.D.C., TN.
PARCEL ID
14507007000
P.A.D.C., TN

37
MOSLEY, TIMOTHY L. &
LYNDA LEROUE
BOOK 8973,
PAGE 874
R.O.D.C., TN.
PARCEL ID
14507007100
P.A.D.C., TN


40
ROBINSON,
PHILLIP R.
ET UX
BOOK 6602,
PAGE 935
R.O.D.C., TN.
PARCEL ID
14507007400
P.A.D.C., TN

39
PARCEL ID
14507007300
P.A.D.C., TN
AREA: 50073.20
S.F. OR
1.15 ACRES±


LOT COVERAGE = 7,980 SF
LOT SIZE = 50,073 SF (1.15 AC)
30% OF 50,073 SF = 15,022 SF

38
STOUT, RICHARD H. &
KATHERINE M.
INSTRUMENT#
20101026-0085719
R.O.D.C., TN.
PARCEL ID
14507007200
P.A.D.C., TN

EXISTING
DWELLING
#1155



3




Snyder Engineering, PLLC
CIVIL ENGINEERING SERVICES
228 Spence Lane
Nashville, TN 37210
Phone 615-383-1699
Fax 615-297-7184
tomsnyder@comcast.net

SITE PLAN
NEW RESIDENCE
1167 Travelers Ridge Drive
Nashville, TN 37220
34th Council District
City of Oak Hill
Davidson County, TN
Parcel ID 14507007300

DR.	CHK.	DATE	DESCRIPTION

FILE NO. III3-21
3




SITE BENCHMARK
TOP OF MANHOLE
ELEV. 755.74
NAVD 88

PROPOSED 16 LF OF 30" RCP AT 9.06%
INLET EL 764.60
OUTLET EL 763.15
HEADWALLS REQUIRED
MATCH INVERTS WITH CONC. DITCH

SEE METRO NASHVILLE
ROADWAY TRENCH REPAIR
DETAILS WHERE PAVEMENT
IS CUT.

Snyder Engineering, PLLC
CIVIL ENGINEERING SERVICES
228 Spence Lane
Nashville, TN 37210
Phone 615-383-1699
Fax 615-297-7184
tonysnyder@comcast.net




GRADING AND UTILITY PLAN

NEW RESIDENCE

1167 Travelers Ridge Drive
Nashville, TN 37220
34th Council District
Parcel ID 14507007300
City of Oak Hill
Davidson County, TN

DR.	CHK.	DATE	DESCRIPTION

FILE NO. III3-21






NOTE 1:
PROPERTY LINE DITCHES TO BE STABILIZED AT THE TIME OF CONSTRUCTION. USE SMARTDITCH 12" TRAPEZOIDAL HDPE CHANNELS OR APPROVED EQUAL FOR NORTH SIDE DITCH. SOUTH SIDE DITCH TO BE SODDED.

NOTE: GEOTECHNICAL ENGINEER SHALL BE ONSITE PER THE STEEP SLOPE ORDINANCE SECTION 14-238 TO MONITOR CONSTRUCTION. ENGINEER SHALL SUBMIT A GEOTECHNICAL CERTIFICATION LETTER CERTIFYING THE STABILITY OF THE SLOPE AND THE STRUCTURE TO THE CITY OF OAK HILL UPON COMPLETION OF CONSTRUCTION AND PRIOR TO THE ISSUANCE OF A CERTIFICATE OF OCCUPANCY.



NET ADDITIONAL IMPERVIOUS AREA = 7,980 SF
 TOTAL AREA (INP + PERV) DRAINING TO RAIN GARDEN = 8,967 SF
 ADDED IMPERVIOUS AREA MITIGATED BY EXISTING TREES:
 20% OF 8,967 SF = 1,793 SF
 1,793 SF / 50 SF PER TREE = 36 TREES
 BY INSPECTION THERE ARE MORE THAN 36 TREES REMAINING
 THAT ARE AT LEAST 6" DBH.
 AREA TO BE TREATED = 8,967 - 1,793 = 7,174 SF
 DEPTH OF SOIL MEDIA = 36 INCHES
 REQUIRED RAIN GARDEN SURFACE AREA = 361 SF
 RAIN GARDEN SURFACE AREA PROVIDED = 390 SF



- CONSTRUCTION STEPS:
1. Locate rain garden(s) where downspouts or driveway runoff can enter garden flowing away from the home. Locate at least 10 feet from foundations, not within the public right of way, away from utility lines, not over septic fields, and not near a steep bluff edge.
 2. Measure the area draining to the planned garden and determine required rain garden surface area from the table on the next page and your planned excavation depth.
 3. Optionally, perform infiltration test according to Section B. If the rate is less than 0.25 in/hr an underdrain will be necessary. If the rate is more than 0.50 in/hr the size of the garden may be decreased 10% for every 0.50 in/hr infiltration rate increase above 0.50 in/hr.
 4. Measure elevations and stake out the garden to the required dimensions insuring positive flow into garden, the overflow elevation allows for six inches of ponding, and the perimeter of the garden is higher than the overflow point. If the garden is on a gentle slope a berm at least two feet wide can be constructed on the downhill side and/or the garden can be dug into the hillside taking greater care for erosion control at the garden inlet(s).
 5. Remove turf or other vegetation in the area of the rain garden. Excavate garden being careful not to compact soils in the bottom of the garden. Level bottom of garden as much as possible to maximize infiltration area.
 6. Mix compost, topsoil, and some of the excavated subsoil together to make the 'amended soil'. The soil mix should be 1/3 compost, 2/3 native soil (topsoil and subsoil combined).
 7. Fill rain garden with the amended soil, leaving the surface eight inches below your highest surrounding surface. Eight inches allows for 6 inches ponding and 2" of mulch. The surface of the rain garden should be as close to level as possible.
 8. Build a berm at the downhill edge and sides of the rain garden with the remaining subsoil. The top of the berm needs to be level, and set at the maximum ponding elevation.
 9. Plant the rain garden using a selection of plants from elsewhere in this manual.
 10. Mulch the surface of the rain garden with two to three inches of non-floating organic mulch. The best choice is finely shredded hardwood mulch. Pine straw is also an option.
 11. Water all plants thoroughly. As in any new garden or flower bed, regular watering will likely be needed to establish plants during the first growing season.
 12. During construction build the inlet feature as a pipe directly connected to a downspout or use a rock lined swale with a gentle slope. Use of an impermeable liner under the rocks at the end of the swale near the house is recommended to keep water from soaking in at that point. Test the drainage of water from the source to the garden prior to finishing.
 13. Create an overflow at least 10 feet from your property edge and insure it is protected from erosion.

METRO NASHVILLE DEPARTMENT OF WATER SERVICES	NAME/ADDRESS:	RAIN GARDEN SPECIFICATIONS PAGE 1 OF 2
--	---------------	--


Snyder Engineering, PLLC
 CIVIL ENGINEERING SERVICES
 Phone 615-383-1699
 Fax 615-297-7164
 228 Spence Lane
 Nashville, TN 37210
 tonsnyder@comcast.net




RAIN GARDEN DETAIL
NEW RESIDENCE
 Parcel ID 14507007300
 1167 Travelers Ridge Drive
 Nashville, TN 37220
 City of Oak Hill
 Davidson County, TN
 34th Council District


DR.	CHK.	DATE	DESCRIPTION

FILE NO. III3-21
5








PLAN VIEW OF TEMPORARY CONSTRUCTION ROAD




SECTION A-A



DR.	CHK.	DATE	DESCRIPTION


FILE NO. 1113-21

6



SITE BENCHMARK
TOP OF MANHOLE
ELEV. 755.74
NAVD 88

LIMITS OF DISTURBANCE
17,577 SF
0.404 AC



LIMITS OF DISTURBANCE
NEW RESIDENCE
1167 Travelers Ridge Drive
Nashville, TN 37220
34th Council District
Parcel ID 14507007300
City of Oak Hill
Davidson County, TN

DR.	CHK.	DATE	DESCRIPTION

FILE NO. III3-21

7

TREE LIST

TREE #	DBH	DRIP ZONE	
1	12"	25'	
2	8"	20'	—TO BE REMOVED *
3	12"	20'	
4	12"	25'	
5	12"	20'	
6	8"	25'	
7	8"	15'	
8	8"	25'	
9	12"	20'	
10	8"	15'	
11	8"	15'	
12	8"	15'	—TO BE REMOVED *
13	12"	20'	—TO BE REMOVED *
14	18"	25'	—TO BE REMOVED *
15	24"	25'	—TO BE REMOVED *
16	12"	25'	—TO BE REMOVED *
17	8"	20'	—TO BE REMOVED *
18	8"	20'	—TO BE REMOVED
19	8"	15'	—TO BE REMOVED *
20	24"	30'	—TO BE REMOVED *
21	8"	15'	—TO BE REMOVED *
22	12"	20'	—TO BE REMOVED *
23	8"	10'	—TO BE REMOVED
24	12"	DEAD	
25	12"	20'	
26	8"	20'	
27	8"	15'	
28	12"	20'	
29	12"	20'	
30	8"	10'	
31	8"	20'	—TO BE REMOVED
32	12"	15'	—TO BE REMOVED
33	8"	10'	—TO BE REMOVED
34	24"	25'	—TO BE REMOVED
35	8"	15'	—TO BE REMOVED
36	8"	15'	—TO BE REMOVED
37	8"	10'	—TO BE REMOVED
38	12"	20'	—TO BE REMOVED
39	18"	25'	—TO BE REMOVED
40	8"	15'	—TO BE REMOVED
41	12"	20'	—TO BE REMOVED
42	12"	25'	—TO BE REMOVED
43	8"	20'	—TO BE REMOVED
44	8"	20'	—TO BE REMOVED
45	8"	20'	—TO BE REMOVED
46	8"	15'	—TO BE REMOVED
47	24"	30'	—TO BE REMOVED
48	18"	DEAD	
49	24"	25'	
50	8"	10'	
51	8"	20'	—TO BE REMOVED
52	8"	10'	
53	12"	15'	
54	12"	10'	
55	12"	10'	
56	8"	15'	
57	12"	15'	


58	8"	15'	
59	8"	20'	
60	8"	15'	
61	12"	20'	
62	12"	20'	
63	12"	15'	
64	12"	20'	
65	12"	10'	
66	8"	25'	
67	18"	25'	
68	12"	10'	
69	12"	20'	
70	8"	15'	
71	12"	10'	
72	8"	10'	
73	12"	10'	
74	12"	20'	
75	12"	15'	
76	8"	25'	
77	12"	15'	
78	8"	20'	
79	8"	20'	
80	8"	15'	
81	12"	25'	
82	3"	5'	
83	3"	7'	
84	3"	5'	
85	3"	5'	
86	3"	6'	
87	3"	5'	
88	3"	7'	
89	3"	4'	
90	3"	5'	
91	8"	5'	
92	3"	4'	
93	3"	6'	
94	3"	7'	
95	3"	5'	
96	3"	4'	
97	3"	5'	
98	3"	5'	
99	3"	4'	
100	3"	6'	
101	3"	7'	
102	3"	5'	
103	12"	32'	
104	3"	5'	
105	3"	7'	
106	3"	5'	
107	3"	5'	
108	3"	6'	
109	8"	5'	
110	3"	7'	
111	3"	4'	
112	3"	5'	
113	3"	5'	
114	3"	4'	
115	3"	6'	—TO BE REMOVED
116	3"	7'	—TO BE REMOVED
117	3"	5'	—TO BE REMOVED

118	3"	4'	
119	3"	5'	
120	3"	5'	—TO BE REMOVED
121	3"	4'	—TO BE REMOVED
122	3"	6'	
123	3"	7'	—TO BE REMOVED
124	3"	5'	—TO BE REMOVED
125	3"	4'	—TO BE REMOVED
126	3"	6'	
127	3"	7'	—TO BE REMOVED
128	3"	5'	—TO BE REMOVED
129	3"	4'	—TO BE REMOVED
130	3"	5'	—TO BE REMOVED
131	3"	5'	—TO BE REMOVED
132	3"	4'	—TO BE REMOVED
133	3"	6'	—TO BE REMOVED
134	3"	7'	—TO BE REMOVED
135	3"	5'	—TO BE REMOVED
136	10"	16'	—TO BE REMOVED
137	8"	14'	
138	3"	4'	—TO BE REMOVED
139	3"	6'	—TO BE REMOVED
140	3"	7'	—TO BE REMOVED
141	3"	5'	
142	3"	4'	—TO BE REMOVED
143	3"	5'	—TO BE REMOVED
144	3"	5'	—TO BE REMOVED
145	3"	4'	
146	3"	6'	—TO BE REMOVED

147	3"	7'	
148	12"	20'	
149	8"	4'	
150	3"	6'	—TO BE REMOVED
151	3"	7'	—TO BE REMOVED
152	3"	5'	—TO BE REMOVED
153	3"	4'	—TO BE REMOVED
154	3"	5'	
155	3"	5'	
156	3"	4'	
157	3"	6'	
158	3"	7'	
159	3"	5'	
160	3"	5'	
161	3"	4'	
162	8"	5'	
163	3"	5'	
164	3"	4'	
165	11"	6'	
166	3"	7'	
167	3"	5'	
168	3"	7'	
169	12"	28'	

170	3"	5'
171	3"	4'
172	3"	5'
173	3"	4'
174	3"	6'
175	3"	7'
176	3"	5'
177	3"	3'
178	3"	8'


* DESIGNATES TREES THAT ARE 8" DBH OR GREATER TO BE REMOVED IN THE FRONT YARD (11 TREES)
 LOT AREA = 50,073 SF (1.15 AC)
 EXISTING TREE COVERAGE = 78%
 PROPOSED TREE COVERAGE = 54%
 PROPOSED RETAINED TREES = 69%
 TREE PROTECTION FENCING = T T T T T T T
 TOTAL TREE DBH TO BE REMOVED = 457 INCHES



TREE TO BE REMOVED
 TREE TO BE PROTECTED AND RETAINED
 TREE PROTECTION FENCING SEE NOTE THIS SHEET


NOTE:
 TREE PROTECTION FENCING TO INCLUDE 4' HIGH CHAIN LINK FENCE WITH METAL POSTS AT 8' MIN. SPACING 6' LONG WITH 2' IN-GROUND EMBEDMENT.

Snyder Engineering, PLLC
 CIVIL ENGINEERING SERVICES
 228 Spence Lane
 Nashville, TN 37210
 Phone 615-383-1699
 Fax 615-297-7184
 tonymnyder@comcast.net




TREE REMOVAL AND PROTECTION PLAN
NEW RESIDENCE
 1167 Travelers Ridge Drive
 Nashville, TN 37220
 34th Council District
 Parcel ID 14507007300
 City of Oak Hill
 Davidson County, TN

DR.	CHK.	DATE	DESCRIPTION





- GENERAL NOTES PAGE 2 OF 3
- PRIOR TO PLACEMENT OF CRUSHED STONE OR FLOWABLE FILL THE DEPARTMENT OF PUBLIC WORKS PERMITS OFFICE WILL BE NOTIFIED AND AN INSPECTION OF THE TRENCH WILL BE MADE BY A REPRESENTATIVE OF THE DEPARTMENT OF PUBLIC WORKS PERMITS OFFICE. AT THE COMPLETION OF THE INSTALLATION OF THE CRUSHED STONE OR FLOWABLE FILL, THE DEPARTMENT OF PUBLIC WORKS PERMITS OFFICE WILL BE NOTIFIED AND AN INSPECTION OF THE BACKFILL WILL BE MADE BY A REPRESENTATIVE OF THE DEPARTMENT OF PUBLIC WORKS. AFTER ACCEPTANCE OF THE BACKFILL BY THE REPRESENTATIVE OF THE DEPARTMENT OF PUBLIC WORKS PERMITS OFFICE, THE ASPHALT PAVEMENT CAN BE APPLIED.
 - INSPECTION PERSONNEL OF THE DEPARTMENT OF PUBLIC WORKS SHALL BE NOTIFIED BY CONTRACTOR/PERMITEE AT LEAST TWO (2) DAYS PRIOR TO REQUEST FOR INSPECTION.
 - THE WORK PERFORMED SHALL BE FREE FROM WORKMANSHIP DEFECTS FOR A PERIOD OF ONE (1) YEAR AFTER THE DATE OF ACCEPTANCE BY THE DEPARTMENT OF PUBLIC WORKS PERMIT OFFICE.
 - EXISTING PAVEMENTS, BASES, CURBS & GUTTERS AND SIDEWALKS SHALL BE CUT AND BROUGHT TO A NEAT LINE BY USE OF AN AIR HAMMER, SAW OR OTHER SUITABLE EQUIPMENT. EXPANSION JOINTS REMOVED SHALL BE REPLACED.
 - THE MINIMUM WIDTH TO BE TRIMMED ON EACH SIDE OF THE TRENCH LINE, AS SEEN IN THE SECTION MAY BE WAIVED OR AMENDED UPON APPROVAL OF THE METRO DEPARTMENT OF PUBLIC WORKS, HOWEVER, A MINIMUM WIDTH OF REPLACEMENT SHALL BE 4'-0" TO ALLOW FOR A ROLLER.
 - IF PERMANENT PAVEMENT REPAIRS CANNOT BE MADE WITHIN THREE (3) DAYS, THEN TEMPORARY REPLACEMENT SHALL BE MADE WITH 2" COLD MIX. PERMANENT PAVEMENT REPAIR TO BE COMPLETED WITHIN THE REQUIRED TIME PERIOD AS PER METRO CODE 13.20.
 - ALL EXCAVATIONS MADE WITHIN PUBLIC RIGHT-OF-WAY REQUIRE EXCAVATIONS AND STREET CLOSURE PERMITS FROM THE DEPARTMENT OF PUBLIC WORKS PRIOR TO COMMENCING WORK AS PER METRO CODE 13.20.
 - FLOWABLE FILL WILL BE REQUIRED ON ALL ARTERIALS, COLLECTORS AND DOWNTOWN STREETS. FLOWABLE FILL SHALL MEET THE REQUIREMENTS IN TENNESSEE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS SECTION 204, EXCEPT AS MODIFIED BY PUBLIC WORKS TECHNICAL SPECIFICATIONS 02225, LATEST REVISION.
 - IN THE EVENT OF ANY CONFLICT, DISCREPANCY, OR INCONSISTENCY AMONG THE PLANS AND THESE STANDARD DETAILS, THE REQUIREMENTS OF THE STANDARD DETAILS SHALL GOVERN.
 - ALL REPAIRS SHALL INCLUDE FULL LANE WIDTH RESURFACING EXCEPT WHEN UTILIZING INFRARED TECHNOLOGY. SEE INFRARED SPECIFICATIONS ATTACHED. THERE WILL BE A MAXIMUM OF 40 FT LONGITUDINAL REPAIR WHEN USING INFRARED TECHNOLOGY ON AN EXCAVATED PATCH.
 - ALL REPAIRS SHALL UTILIZE A 1-FOOT CUTBACK ON ALL SIDES EXCEPT THE EDGE OF PAVEMENT.
- NOT TO SCALE
- | | | |
|---|--------------------------------------|-------------------|
| METROPOLITAN GOVERNMENT OF NASHVILLE AND DAVIDSON COUNTY DEPARTMENT OF PUBLIC WORKS | FLUSH TRENCH REPAIR WITH STONE NOTES | DWG. NO. ST-270a |
| DIR. OF ENG.: <i>Alvin M. King</i> | DATE: 7/15/15 | REVISED: 04/01/08 |
| | | REVISED: 11/17/08 |
| | | REVISED: 03/24/10 |
| | | REVISED: 07/15/15 |

- GENERAL NOTES CONTINUED: PAGE 3 OF 3
- NEW UTILITY CUTS WILL BE MILLED AND PAVED TO ANY EXISTING UTILITY CUT OR DAMAGED PAVEMENT WITHIN 10-FEET. IF EXISTING CUT OR DAMAGED PAVEMENT IS LESS THAN 10-FEET IN LENGTH, THE EXISTING CUT OR DAMAGED PAVEMENT SHALL ALSO BE MILLED AND PAVED.
 - ASPHALT REPAIR ADJACENT TO CURBS AND CUTTER ALONG A ROADWAY GREATER THAN 24-INCHES SHALL HAVE FULL LANE WIDTH PAVING.
 - WHEN GRADED STONE (I.E. #57, #67, #78 STONE) IS USED THERE IS GENERALLY NO COMPACTION EQUIPMENT REQUIRED. THE MATERIAL DOES, HOWEVER, NEED TO BE PUT IN THE TRENCH IN APPROXIMATELY 12-INCH LIFTS.
 - GRADED STONE PLACED IN TRENCH SHOULD BE CAPPED WITH 8 TO 12-INCHES OF PUG MIX (MIX IS ESSENTIALLY TYPE A BASE, GRADE D, OR MORE COMMONLY KNOWN AS "CRUSHER RUN"). SEE TDOT STANDARD SPECIFICATION 303.07.
 - THE PUG MIX SHOULD BE COMPACTED IN 6-INCH LIFTS WITH A STEEL SHELL ROLLER OR OTHER MECHANICAL VIBRATORY COMPACTION EQUIPMENT. SEE TDOT STANDARD SPECIFICATIONS 303.08 AND 303.09. MATERIAL SHOULD BE ALLOWED TO CURE UNTIL ALL THE MOISTURE IS GONE FROM STONE (USUALLY 24-48 HOURS).
 - THE TRENCH SHOULD THEN HAVE 11-INCHES OF BINDER PLACED LEVEL WITH THE ROADWAY IN A MINIMUM OF TWO (2) LIFTS AND COMPACTED WITH MECHANICAL COMPACTION EQUIPMENT.
 - THE BINDER SURFACE SHALL BE MILLED OR HEATED USING INFRARED TECHNOLOGY TWO 2-INCHES IN DEPTH AND REPLACED WITH TWO (2) INCHES OF SURFACE MIX AND COMPACTED WITH MECHANICAL COMPACTION EQUIPMENT.
 - INTERSECTION REPAIRS WILL ONLY REQUIRE FULL LANE WIDTH PAVING.
 - ANY DISTURBED PAVEMENT MARKINGS MUST BE RESTORED TO CURRENT METRO STANDARDS.
 - DIAGONAL REPAIRS WILL BE REQUIRED TO BE SQUARED OFF AND MILLED AND PAVED. NO INFRARED TECHNOLOGY ALLOWED ON THIS TYPE OF REPAIR.
 - ALL LONGITUDINAL REPAIRS MORE THAN 40 FT IN LENGTH WILL BE REQUIRED TO BE MILLED AND PAVED.
 - FOR ANY DISCREPANCIES OR VARIATIONS FROM SPECIFICATIONS, OBTAIN APPROVAL FROM THE DEPARTMENT OF PUBLIC WORKS.
 - ALL FILL SHALL MEET MANUFACTURING SPECIFICATIONS, IF APPLICABLE.
- NOT TO SCALE
- | | | |
|---|--------------------------------------|-------------------|
| METROPOLITAN GOVERNMENT OF NASHVILLE AND DAVIDSON COUNTY DEPARTMENT OF PUBLIC WORKS | FLUSH TRENCH REPAIR WITH STONE NOTES | DWG. NO. ST-270a |
| DIR. OF ENG.: <i>Alvin M. King</i> | DATE: 7/15/15 | REVISED: 04/01/08 |
| | | REVISED: 11/17/08 |
| | | REVISED: 03/24/10 |
| | | REVISED: 07/15/15 |



TREE PROTECTION DETAIL



Snyder Engineering, PLLC
CIVIL ENGINEERING SERVICES

Phone 615-383-1699
Fax 615-297-7184
228 Spence Lane
Nashville, TN 37210
tonysnyder@comcast.net

09-20-2022
STATE OF TENNESSEE

NEW RESIDENCE
Parcel ID 14507007300
City of Oak Hill
Davidson County, TN

1167 Travelers Ridge Drive
Nashville, TN 37220
34th Council District


DR.	CHK.	DATE	DESCRIPTION

FILE NO. III3-21

9

TREE TABLE		REMOVED		
PRE-DEVELOPMENT TREE #	DBH	REPLACEMENT CAL. PER	QTY	
1	12"	25"		
2	8"	20"		
3	12"	20"		
4	12"	25"		
5	12"	20"		
6	8"	20"		
7	8"	15"		
8	8"	20"		
9	12"	20"		
10	8"	15"		
11	8"	15"		
12	8"	15"		
13	12"	20"	5"	3
14	12"	20"	5"	4
15	24"	25"	5"	5
16	12"	20"		
17	12"	20"	5"	2
18	8"	20"	5"	2
19	12"	20"	5"	2
20	24"	20"	5"	5
21	8"	15"	5"	2
22	12"	20"		
23	8"	10"	5"	2
24	12"	BEAD	-	-
25	12"	20"		
26	8"	20"		
27	8"	15"		
28	12"	20"		
29	12"	20"		
30	8"	10"		
31	8"	20"	5"	2
32	12"	15"	5"	3
33	8"	10"	5"	2
34	24"	25"	5"	2
35	8"	15"	5"	2
36	8"	15"	5"	2
37	8"	10"	5"	2
38	12"	20"	5"	3
39	12"	20"	5"	3
40	8"	15"	5"	2
41	12"	20"	5"	3
42	12"	20"	5"	3
43	8"	20"	5"	2
44	8"	20"		
45	8"	20"		
46	8"	15"		
47	24"	30"	5"	5
48	12"	BEAD	-	-
49	24"	25"		
50	8"	10"		
51	8"	20"		
52	8"	10"		
53	12"	15"		
54	12"	10"		
55	12"	10"		
56	8"	15"		
57	12"	15"		
58	8"	15"		
59	8"	20"		
60	8"	20"		
61	12"	20"		
62	12"	18"		
63	12"	18"		
64	12"	20"		
65	8"	25"		
66	8"	25"		
67	12"	25"		
68	8"	15"		
69	12"	20"		
70	8"	15"		
71	12"	10"		
72	8"	10"		
73	12"	10"		
74	12"	20"		
75	12"	15"		
76	8"	25"		
77	12"	15"		
78	8"	20"		
79	8"	15"		
80	8"	15"		
81	12"	25"		
82	8"	20"		
83	8"	20"		
84	8"	5"	5"	1
85	8"	5"	5"	1
86	8"	5"	5"	1
87	8"	5"		
88	8"	5"		
89	8"	5"		
90	8"	5"		
91	8"	5"		
92	8"	4"		
93	8"	4"		
94	8"	4"		
95	8"	5"		
96	8"	4"		
97	8"	4"		
98	8"	5"		
99	8"	4"		
100	8"	5"		
101	8"	7"	5"	1
102	8"	5"		
103	8"	30"		
104	8"	5"		
105	8"	7"		
106	8"	5"		
107	8"	5"		
108	8"	5"		
109	8"	5"		
110	8"	7"		
111	8"	5"		
112	8"	5"		
113	8"	5"		
114	8"	4"		
115	8"	6"		
116	8"	6"	5"	1
117	8"	6"	5"	1
118	8"	4"		
119	8"	5"	5"	1
120	8"	5"	5"	1
121	8"	4"	5"	1
122	8"	5"		
123	8"	6"	5"	1
124	8"	5"		
125	8"	6"		
126	8"	6"		
127	8"	7"	5"	1
128	8"	5"	5"	1
129	8"	4"	5"	1
130	8"	5"	5"	1
131	8"	5"	5"	1
132	8"	4"		
133	8"	6"		
134	8"	7"		
135	8"	5"	5"	1
136	10"	16"		
137	8"	14"		
138	8"	4"	5"	1
139	8"	6"	5"	1
140	8"	7"		
141	8"	5"	5"	1
142	8"	4"	5"	1
143	8"	5"	5"	1
144	8"	5"		
145	8"	4"		
146	8"	6"		
147	8"	7"		
148	10"	20"		
149	8"	4"		
150	8"	6"		
151	8"	5"		
152	8"	5"		
153	8"	4"		
154	8"	5"		
155	8"	5"		
156	8"	4"		
157	8"	5"		
158	8"	7"		
159	8"	5"		
160	8"	5"		
161	8"	4"		
162	8"	5"		
163	8"	5"		
164	8"	4"		
165	11"	6"		
166	8"	5"		
167	8"	5"		
168	8"	5"		
169	12"	20"		
170	8"	5"		
171	8"	4"		
172	8"	5"		
173	8"	4"		
174	8"	6"		
175	8"	7"		
176	8"	5"		
177	8"	5"		
178	8"	8"		

PREPARED BY:
CAMPBELL, McRAE
& ASSOCIATES,
SURVEYING, INC.
P.O. BOX 41153
NASHVILLE, TN, 37204
PH. 615-298-2424
EMAIL cmas@att.net



I HEREBY CERTIFY THAT THIS IS A CATEGORY I SURVEY WITH THE RATIO OF PRECISION OF THE UNADJUSTED SURVEY BEING 1: 22,000. THIS SURVEY WAS DONE IN COMPLIANCE WITH THE CURRENT STANDARDS OF PRACTICE ADOPTED BY THE TENNESSEE STATE BOARD OF EXAMINERS FOR LAND SURVEYORS.

JOHN ALAN HOOD
TN. R.L.S.#1838

BOUNDARY SURVEY
LOT 39 REVISED PLAN OF INNS OF GRANNY WHITE R.O.D.C., TN. BOOK 6250, PAGE 450 AMENDED IN BOOK 6900, PAGE 125 R.O.D.C., TN

PROPERTY LOCATED
34TH COUNCIL DISTRICT OF NASHVILLE, DAVIDSON COUNTY TENNESSEE, IN THE CITY OF OAK HILL ON THE WESTERLY MARGIN OF TRAVELLERS RIDGE DRIVE, SOUTH OF GRANNY WHITE PIKE

PROPERTY ADDRESS:
1167 TRAVELERS RIDGE DRIVE NASHVILLE, TN 37220


DEED REFERENCE:
INSTRUMENT # 20210416-0051064 R.O.D.C., TN.

PARCEL ID
14507007300 P.A.D.C., TN.

DATE: 8-29-2022

SCALE: 1" = 40'

PREPARED FOR:
SABALO DEVELOPMENT, LLC



SUMMARY OF PRE-DEVELOPMENT TREE CANOPY COVER AS A PERCENTAGE OF THE LOT SIZE
TOTAL LOT AREA 5007320 S.F.
PRE-DEVELOPMENT TREE CANOPY COVERAGE 47308 S.F.
47308 / 5007320 = 0.94

TREE PROTECTION

ANY HOLDER OF A PERMIT ISSUED FROM THE CITY OF OAK HILL TENNESSEE FOR LAND DISTURBANCE ACTIVITIES AT A SITE, AND ALL SUBCONTRACTORS WORKING FOR A PERMIT HOLDER, UNLESS OTHERWISE EXEMPT, SHALL WHOLLY ABIDE BY: CITY OF OAK HILL MUNICIPAL CODE TITLE 14, SECTIONS 901-909 FOR WOODLAND AND TREE PROTECTION.

BARRICADES SHALL BE INSTALLED A MINIMUM OF TEN FEET (10') FROM A PROTECTED TREE OR AT THE DESIGNATED PROTECTED ROOT ZONE AS SHOWN ON THE APPROVED SITE PLAN.

THE CODE COMPLIANCE OFFICER MAY ALLOW MINOR MODIFICATIONS TO THIS STANDARD BASED UPON SPECIFIC SITE CONFIGURATION ISSUES.

ALL PERMIT APPLICATIONS SHALL INCLUDE A CERTIFIED ARBORIST'S REPORT FOR AFFECTED TREES.

PROPERTY IS ZONED RESIDENTIAL "C*" WITHIN THE JURISDICTION OF THE CITY OF OAK HILL, TN. SETBACKS FOR RESIDENTIAL "C*" ZONING TAKEN FROM THE CITY OF OAK HILL, TN OFFICIAL ZONING MAP ADOPTED BY ORDINANCE 02-90 ON FEBRUARY 27, 2018.

MINIMUM LOT AREA = 1 ACRE
MAXIMUM LOT COVERAGE = 15246 S.F. OR 35%
MAXIMUM HEATED/COOLED SPACE = 60% UP TO 9500
MAXIMUM HEIGHT = 2 1/2 STORIES / 36'
MINIMUM YARD REQUIREMENTS:
FRONT = WHICHEVER IS GREATER 75' OR THE AVERAGE OF 4 LOTS, WHICH ARE MOST ADJACENT, WITH LIKE-FACING HOMES THEREIN (PER SECTION 14-121.F OF ZONING ORDINANCE)

CONTEXTUAL SETBACK SUMMARY
77.1 + 51.7 + 61.1 + 76.1 / 4 = 66.5

SIDE = 30'
REAR = 60'

MINIMUM FRONT LOT LINE = 100'
MAXIMUM LOT DEPTH/LOT WIDTH RATIO = 4:1

VERIFY SETBACKS WITH CODES BEFORE DESIGN OR CONSTRUCTION DECISIONS ARE MADE.

BY GRAPHIC SCALING FROM THE LATEST FEMA / FLOOD INSURANCE RATE MAP THIS PROPERTY IS NOT LOCATED IN A F.E.M.A. / F.I.R.M SPECIAL FLOOD HAZARD AREA. MAP 47037C PANEL 0358"H EFFECTIVE DATE : 4-5-17

CONTOURS ARE SHOWN AT 2 FOOT INTERVALS ARE WERE GENERATED FROM A COMBINATION OF A RADIAL TOPOGRAPHIC SURVEY PERFORMED ON SITE USING EDM EQUIPMENT AND A TOPCON HIPER-SR DUAL FREQUENCY GPS RECEIVER TIED TO THE T.D.D.T. GNSS REFERENCE NETWORK AND FROM DIGITAL ELEVATION MODELS FROM TINLIDAR FLOWN IN 2016. TILE #1716629NE & 1716629SE ELEVATION DATUM NAVD 88, GEOID 12A

LEGEND
W= WATER LINE (RECORD)
S= SEWER LINE (RECORD)
OH= OVERHEAD LINES
E/P = EDGE PAVEMENT
U/P = UTILITY POLE
F.H. = FIRE HYDRANT
M.B.S.L. = MINIMUM BUILDING SETBACK LINE

ROBINSON, PHILLIP R. ET UX
BOOK 6602, PAGE 934
R.O.D.C., TN
PARCEL ID 14507007400
P.A.D.C., TN

RESUBDIVISION OF LOTS 34 & 35, INNS OF GRANNY WHITE
BOOK 6900, PAGE 412
R.O.D.C., TN

IDAMNIDES SOCRATES A. INSTRUMENT# 20040223-0020115
R.O.D.C., TN
PARCEL ID 14507006900
P.A.D.C., TN

WILLIAMSON FAMILY REVOCABLE LIVING TRUST INSTRUMENT# 20150901-008439
R.O.D.C., TN
PARCEL ID 14507007000
P.A.D.C., TN

STOUT, RICHARD H. & KATHERINE M.
INSTRUMENT# 20101026-0085719
R.O.D.C., TN
PARCEL ID 14507007200
P.A.D.C., TN

MOSLEY, TIMOTHY L. & LYNDA LEROUX
BOOK 6973, PAGE 874
R.O.D.C., TN
PARCEL ID 14507007100
P.A.D.C., TN



bgc construction travelers ridge

1167 TRAVELERS RIDGE NASHVILLE, TN 37220
MAY 24, 2021

SHEET INDEX

GENERAL	
601	COVER, INDEX, SITE PLAN
602	GENERAL NOTES, SYMBOLS & ABBREVIATIONS
ARCHITECTURAL	
ASITE	ARCHITECTURAL SITE PLAN
A000	FOUNDATION PLAN
A100	GARAGE PLAN
A101	FIRST FLOOR PLAN
A102	SECOND FLOOR PLAN
A103	ROOF PLAN
A200	EXTERIOR ELEVATIONS
A201	EXTERIOR ELEVATIONS
A700	DOOR & WINDOW SCHEDULES

PROJECT NOTES

AREAS:

FIRST FLOOR: 3,475 GROSS SQUARE FEET (CONDITIONED)
SECOND FLOOR: 1,533 GROSS SQUARE FEET (CONDITIONED)
GARAGE: 1,026 GROSS SQUARE FEET

CITY OF OAK HILL INFORMATION

ZONING AREA: RESIDENTIAL 'C'
GROSS FLOOR AREA RATIO:
TOTAL BUILDING AREA: 6,034 GROSS SQ FT
TOTAL LOT AREA: 50,073.20 SQ FT
GROSS FAR: 6,034 / 50,073.20 = 0.12 (12%)
ALLOWABLE GROSS FAR: 18%

ZINC
ARCHITECTURE



8230 FREDERICKS LANE DRIVE
NASHVILLE, TN 37215
P: 615.418.2772
WWW.ZINCARCH.COM

The ideas, designs, details, and specifications contained in these documents are the property of Zinc Architecture LLC. These documents constitute instruments of service of which Zinc Architecture retains sole ownership and may not be reproduced without the expressed written consent of an authorized agent of Zinc Architecture.

PROJECT No. 2109

bgc
travelers ridge
1167 travelers ridge
nashville, tn 37220

MAY 24, 2021
ISSUE FOR PERMIT



ISSUE FOR PERMIT 05.24.21

COVER & INDEX
ZONING INFO

SHEET No:
601

DATE: 05.24.2021

TYPICAL HATCHES

ELEVATION SECTION CERAMIC TILE/QUARRY TILE BRICK METAL PANEL CMU RUNNING BOND GLAZING WOOD BLOCKING CUT STONE GRANULAR FILL STEEL (LARGE SCALE) SPRAY FOAM INSULATION FINISHED WOOD FLYWOOD (LARGE SCALE) CONCRETE INSULATION FLYWOOD (SMALL SCALE) RIGID INSUL. CONCRETE BLOCK GYPSUM BD/PLASTER MINERAL FIBER INSUL.

ARCHITECTURAL SYMBOLS

ARCHITECTURAL SYMBOLS: EQUIPMENT OWNER FURNISHED, DOOR NUMBER, ELEVATION NOTE, WINDOW TAG, DEMO NOTE, KEYNOTE, REVISION, NORTH ARROW, WALL TAG, INTERIOR ELEVATION, EXTERIOR ELEVATION, FINISH TAG, ROOM NUMBER, SPACE NAME, COLUMN NUMBER.

NOTES

ROOFING: CONTRACTOR TO COORDINATE THE FINAL SELECTION OF ROOFING MATERIAL WITH THE OWNER... ALL ROOF SHEATHING TO BE 5/8" CDX PLYWOOD WITH EDGE CLIPS AND TWO LAYERS OF 15 POUND ROOF FELT. ALL VALLEYS TO BE OVERLAPPED ROOFING. ALL ROOFING NAILS TO BE RUST-RESISTANT GALVANIZED OR BETTER... SPECIALTY SYSTEMS: CONTRACTOR TO COORDINATE ALARM SYSTEM REQUIREMENTS WITH OWNER... MECHANICAL SYSTEMS: PRIOR TO INSTALLATION OF THE SYSTEM, ARCHITECT AND OWNER SHALL REVIEW AND APPROVE A LAYOUT DRAWING SHOWING DUCT RUNS... ELECTRICAL SYSTEM: THIS IS A "PERFORMANCE SPECIFICATION". THE CONTRACTOR SHALL EXAMINE THE DRAWINGS TO ASCERTAIN THE POWER AND LOAD REQUIREMENTS...

GENERAL: THESE DRAWINGS ARE ISSUED WITHOUT SPECIFICATIONS. ALL MATERIALS AND WORKMANSHIP SHALL BE EQUAL OR ABOVE ACCEPTED STANDARDS FOR CUSTOM GRADE RESIDENTIAL CONSTRUCTION. THE DRAWINGS ARE INTENDED TO ESTABLISH THE DESIGN INTENT BUT NOT COMPLETELY DEFINE THE MEANS AND MANNER OF CONSTRUCTION. CONTRACTOR SHALL INCLUDE IN HIS CONTRACT PROPOSAL REASONABLE ALLOWANCES FOR ITEMS, EQUIPMENT, OR MATERIALS NOT YET SPECIFIED... CONTRACTOR SHALL NOTIFY ARCHITECT OF ANY INCONSISTENCIES OR CONFLICTS IN THE DRAWINGS... CONTRACTOR SHALL EMPLOY A LICENSED SURVEYOR FOR PROPER HOUSE SITING... CONTRACTOR SHALL COORDINATE ANY SITE AND LANDSCAPE WORK WITH THE OWNER OR OWNER'S REPRESENTATIVE... CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND COORDINATE WITH ALL TRADES / SUBCONTRACTORS... CONTRACTOR SHALL VERIFY THE LOCATION(S) OF ALL EQUIPMENT AS WELL AS DIMENSIONS OF EQUIPMENT...

ARCHITECTURAL ABBREVIATIONS

Table of architectural abbreviations with columns for various terms like ABOVE FINISHED FLOOR, ACCESS, ACCESS FLOOR, ACCESS PANEL, etc., and their corresponding abbreviations.

GENERAL CONCRETE: ALL CONCRETE SHALL BE STANDARD WEIGHT 3,000 PSI COMPRESSIVE STRENGTH AT 28 DAYS UNLESS OTHERWISE NOTED. CONSTRUCTION OR CONTROL JOINTS SHALL BE PROVIDED IN SLABS ON GRADES... REINFORCING BARS SHALL BE DEFORMED BILLET STEEL BARS COMPLYING WITH ASTM A615, MINIMUM GRADE 60. WELDED WIRE FABRIC SHALL CONFORM TO ASTM A-82 AND A-125... CONCRETE FOOTINGS: IF, AFTER EXCAVATION, THE CONDITION OF THE SOIL INDICATES A SAFE BEARING CAPACITY OF LESS THAN 2,500 PSF... ALL AGGREGATES TO BE HARDROCK TO MEET ASTM C83.

REVISIONS table with columns: NO., DATE, DESCRIPTION. Includes notes on soil poisoning, perimeter trench, and roof penetrations.

ROBINSON, PHILLIP R. ET UX
 BOOK 6602,
 PAGE 935
 R.O.D.C., TN.
 PARCEL ID
 14507007400
 P.A.D.C., TN



8

ABOU-ZEID, ELIAS &
 BOURSOU LIAN, LANA JI
 INSTRUMENT#
 20160830-0090648
 R.O.D.C., TN.
 PARCEL ID
 14507004700
 P.A.D.C., TN

ZINC
 ARCHITECTURE

8230 FREDERICKS LANE DRIVE
 NASHVILLE, TN 37215
 P: 615.418.2772
 WWW.ZINCARCH.COM

The ideas, designs, details, and specifications contained in these documents are the property of Zinc Architecture LLC. These documents constitute instruments of service of which Zinc Architecture retains sole ownership and may not be reproduced without the expressed written consent of an authorized agent of Zinc Architecture.

PROJECT No. 2109

bgc
 travelers ridge
 1167 travelers ridge
 nashville, tn 37220


**MAY 24, 2021
 ISSUE FOR PERMIT**

REVISIONS
 NO. DATE DESCRIPTION

SITE PLAN

SHEET No:
 A-SITE

DATE: 05.24.2021



SITE PLAN

1

**MAY 24, 2021
ISSUE FOR PERMIT**


REVISIONS		
NO.	DATE	DESCRIPTION

FOUNDATION PLAN







SHEET No:
A000

DATE: 06.21.2021

- GENERAL NOTES:**
1. ALL WALLS 8" REINFORCED CONCRETE
 2. CONTRACTOR TO COORDINATE LOCATION OF H.V.A.C. UNITS & ASSOCIATED CONG. PADS W/ ARCHITECT
 3. CRAWL SPACE IS UNVENTED. PROVIDE CONTINUOUSLY OPERATED MECHANICAL EXHAUST VENTILATION AT A RATE EQUAL TO 1 CFM FOR EACH SQ. FT. OF CRAWL SPACE FLOOR AREA. INCLUDE AN AIR PATHWAY / TRANSFER GRILLE TO CONDITIONED SPACE. INSULATE PERIMETER WALLS OF CRAWL SPACE WITH 2" MIN. R-10 RIGID INSULATION
 4. PROVIDE AT LEAST ONE INSULATED, PAINTED, LOCKABLE STEEL CRAWLSPACE ACCESS DOOR, SIZED TO ALLOW FOR INSTALLATION / REMOVAL OF LARGEST PIECE OF EQUIPMENT IN CRAWLSPACE.



FOUNDATION PLAN
1/4" = 0' 2' 4' 8'



LOWER LEVEL PLAN



**MAY 24, 2021
ISSUE FOR PERMIT**


REVISIONS

NO.	DATE	DESCRIPTION
-----	------	-------------

LOWER LEVEL PLAN

SHEET No:
A100

**MAY 24, 2021
ISSUE FOR PERMIT**




REVISIONS

NO.	DATE	DESCRIPTION

FIRST FLOOR PLAN

SHEET No:
A101



SECOND FLOOR PLAN
 1/4" = 1'-0"
 0 2 4 8'

**MAY 24, 2021
 ISSUE FOR PERMIT**


REVISIONS

NO.	DATE	DESCRIPTION
-----	------	-------------

SECOND FLOOR PLAN

SHEET No:
 A102

DATE: 05.24.2021



**MAY 24, 2021
ISSUE FOR PERMIT**


REVISIONS		
NO.	DATE	DESCRIPTION

ROOF PLAN

SHEET No:

A103

DATE: 05.24.2021



NORTH ELEVATION 2



EAST ELEVATION 1


REVISIONS

NO.	DATE	DESCRIPTION


EXTERIOR ELEVATIONS

SHEET No:
A200

DATE: 05.24.2021



SOUTH ELEVATION 2



WEST ELEVATION 1

MAY 24, 2021
ISSUE FOR PERMIT

REVISIONS

NO.	DATE	DESCRIPTION

EXTERIOR ELEVATIONS

SHEET No:
A201

DATE: 05.24.2021

WINDOW SCHEDULE

TAG	WIDTH	HEIGHT	OPERATION	INTERIOR FINISH	EXTERIOR FINISH	MODEL No.	QUANTITY	COMMENTS
A	7'-0"	9'-0"	FIXED	WD	CLAD	-	-	-
B	3'-0"	2'-0"	FIXED	WD	CLAD	-	-	-
C	3'-0"	5'-0"	CASEMENT	WD	CLAD	-	-	EGRESS
D	4'-6"	4'-6"	FIXED	WD	CLAD	-	-	-
E	3'-0"	9'-6"	FIXED	WD	CLAD	-	-	-
F	1'-4"	4'-0"	CASEMENT	WD	CLAD	-	-	-
G	3'-0"	10'-0"	FIXED	WD	CLAD	-	-	SIDELIGHT
H	3'-0"	3'-0"	AWNING	WD	CLAD	-	-	-
J	3'-0"	7'-0"	FIXED	WD	CLAD	-	-	-
K	5'-8"	3'-0"	FIXED	WD	CLAD	-	-	-
L	5'-8"	7'-0"	FIXED	WD	CLAD	-	-	-
M	2'-0"	3'-0"	AWNING	WD	CLAD	-	-	-
N	2'-0"	7'-0"	FIXED	WD	CLAD	-	-	-
P	3'-0"	3'-0"	FIXED	WD	CLAD	-	-	-
Q	3'-0"	6'-0"	CASEMENT	WD	CLAD	-	-	EGRESS
R	5'-8"	3'-0"	FIXED	WD	CLAD	-	-	-
S	5'-8"	6'-0"	FIXED	WD	CLAD	-	-	-
T	2'-0"	3'-0"	AWNING	WD	CLAD	-	-	-
U	2'-0"	6'-0"	CASEMENT	WD	CLAD	-	-	-
V	4'-4"	6'-0"	CASEMENT	WD	CLAD	-	-	-
W	1'-6"	8'-0"	CASEMENT	WD	CLAD	-	-	-
X	4'-8"	8'-0"	FIXED	WD	CLAD	-	-	-
Y	4'-0"	9'-0"	FIXED	WD	CLAD	-	-	-
Z	8'-0"	8'-0"	FIXED	WD	CLAD	-	-	-
AA	4'-0"	2'-0"	FIXED	WD	CLAD	-	-	-
BB	4'-0"	10'-0"	FIXED	WD	CLAD	-	-	-
CC	10'-0"	10'-0"	FIXED	WD	CLAD	-	-	-
DD	3'-6"	9'-0"	FIXED	WD	CLAD	-	-	-
EE	3'-4"	2'-6"	FIXED	WD	CLAD	-	-	-
FF	3'-4"	5'-6"	CASEMENT	WD	CLAD	-	-	EGRESS
GG	2'-0"	8'-0"	CASEMENT	WD	CLAD	-	-	-
HH	6'-10"	6'-0"	FIXED	WD	CLAD	-	-	-
JJ	2'-8"	3'-0"	AWNING	WD	CLAD	-	-	-
KK	2'-8"	3'-0"	FIXED	WD	CLAD	-	-	-
LL	2'-6"	3'-0"	AWNING	WD	CLAD	-	-	-
MM	2'-6"	3'-0"	FIXED	WD	CLAD	-	-	-
NN	3'-8"	2'-6"	AWNING	WD	CLAD	-	-	-
PP	3'-8"	6'-6"	FIXED	WD	CLAD	-	-	-
QQ	3'-0"	2'-6"	FIXED	WD	CLAD	-	-	-
RR	3'-0"	5'-6"	CASEMENT	WD	CLAD	-	-	EGRESS

LOWER LEVEL DOOR SCHEDULE

DOOR NO.	DOOR					HDW	NOTES
	WIDTH	HEIGHT	THICKNESS	TYPE	MATERIAL		
001	4'-0"	7'-0"	2"	EXT	WD	GARAGE DOOR	SEE ELEVATIONS FOR STYLE
002	4'-0"	7'-0"	2"	EXT	WD	GARAGE DOOR	SEE ELEVATIONS FOR STYLE
003	4'-0"	7'-0"	2"	EXT	WD	GARAGE DOOR	SEE ELEVATIONS FOR STYLE

FIRST FLOOR DOOR SCHEDULE

DOOR NO.	DOOR					HDW	NOTES
	WIDTH	HEIGHT	THICKNESS	TYPE	MATERIAL		
100	4'-0"	10'-0"	1-3/4"	EXT	WD	ENTRY SET & DEADBOLT	PIVOT DOOR HARDWARE
101	3'-0"	8'-0"	1-3/4"	EXT	WD	ENTRY SET & DEADBOLT	-
102	18'-0"	10'-0"	1-3/4"	EXT	WD	-	SIX PANEL POCKETING DOOR
103	2'-8"	8'-0"	1-3/4"	EXT	WD	ENTRY SET & DEADBOLT	-
104	3'-0"	8'-0"	1-3/4"	EXT	WD	ENTRY SET & DEADBOLT	-
105	3'-0"	8'-0"	1-3/4"	INT	WD	PASSAGE & DEADBOLT	-
106	2'-6"	8'-0"	1-3/4"	INT	WD	PRIVACY	-
107	PR. 1'-8"	8'-0"	1-3/4"	INT	WD	PASSAGE	-
108	2'-8"	8'-0"	1-3/4"	INT	WD	PRIVACY	-
109	3'-6"	10'-0"	1-3/4"	INT	WD	POCKET DOOR	FLUSH WITH CEILING
110	2'-4"	8'-0"	1-3/4"	INT	WD	PRIVACY	-
111	2'-6"	8'-0"	1-3/4"	INT	WD	-	-
112	2'-6"	8'-0"	1-3/4"	INT	WD	-	-
113	2'-4"	8'-0"	1-3/4"	INT	WD	PRIVACY	-

SECOND FLOOR DOOR SCHEDULE

DOOR NO.	DOOR					HDW	NOTES
	WIDTH	HEIGHT	THICKNESS	TYPE	MATERIAL		
200	2'-8"	8'-0"	1-3/4"	INT	WD	PRIVACY	-
201	2'-6"	9'-0"	1-3/4"	INT	WD	PRIVACY / POCKET DR	FLUSH WITH CEILING
202	2'-6"	9'-0"	1-3/4"	INT	WD	PASSAGE / POCKET DR	FLUSH WITH CEILING
203	2'-8"	8'-0"	1-3/4"	INT	WD	PRIVACY	-
204	2'-6"	8'-0"	1-3/4"	INT	WD	PASSAGE	-
205	2'-6"	9'-0"	1-3/4"	INT	WD	PRIVACY / POCKET DR	FLUSH WITH CEILING
206	FR. 2'-0"	8'-0"	1-3/4"	INT	WD	PASSAGE	-
207	FR. 2'-0"	8'-0"	1-3/4"	INT	WD	PASSAGE	-
208	2'-8"	8'-0"	1-3/4"	INT	WD	PRIVACY	-
209	2'-6"	9'-0"	1-3/4"	INT	WD	PRIVACY / POCKET DR	FLUSH WITH CEILING
210	2'-6"	8'-0"	1-3/4"	INT	WD	PASSAGE	-
211	PR. 1'-8"	8'-0"	1-3/4"	INT	WD	PASSAGE	-
212	2'-8"	8'-0"	1-3/4"	INT	WD	PRIVACY	-
213	2'-6"	9'-0"	1-3/4"	INT	WD	PASSAGE / POCKET DR	FLUSH WITH CEILING
214	2'-6"	9'-0"	1-3/4"	INT	WD	PRIVACY / POCKET DR	FLUSH WITH CEILING



8520 FREDERICKS BLVD DRIVE
NASHVILLE, TN 37215
P: 615.418.2772
WWW.ZINCARCH.COM

The ideas, designs, details, and specifications contained in these documents are the property of Zinc Architecture LLC. These documents constitute instruments of service of which Zinc Architecture retains sole ownership and may not be reproduced without the expressed written consent of an authorized agent of Zinc Architecture.

PROJECT No. 2109

bgc
travelers ridge
1167 travelers ridge
nashville, tn 37220

MAY 24, 2021
ISSUE FOR PERMIT

REVISIONS
NO. DATE DESCRIPTION

DOOR & WINDOW SCHEDULES

SHEET No:
A700

DATE: 05.24.2021



**American
Geotechnical and
Environmental, Inc.**

September 14, 2022

Mr. Baird Graham
BGC Construction
2510 Franklin Pike
Nashville, Tennessee 37204

RE: Site Plan Review
Lot 39, Inns of Granny White Subdivision
City of Oak Hill, Tennessee
AG & E File Number: 2022-025

Dear Mr. Graham:

As requested, we have reviewed the Site Grading Plan and the retaining wall design for the above referenced building lot.

The Site Grading Plan was prepared by Snyder Engineering, dated September 13, 2022. This plan complies with the Geotechnical Engineering Study we prepared on May 27, 2022.

We have also prepared the structural plans and details for the retaining walls. These details are enclosed with this letter.

Thank you for the opportunity to be of service to you in this matter. If you should have any questions concerning this or any other matter, please feel free to contact us at your convenience.

Sincerely yours,

AMERICAN GEOTECHNICAL & ENVIRONMENTAL, INC.




Robert T. Stickney, P.E.
President

Enclosure

P. O. Box 681237 • Franklin, TN 37068-1237

(615) 791-9768 • Email: agande@comcast.net

Extend wall and veneer 6 inches above ground surface



Height	A	B	C	Top Reinforcement Each Way	Bottom Reinforcement Each Way	D	Wall Reinforcement Each Way
4' 0"	3' 5"	1' 4"	1' 0"	#4 @ 9" o/c	#4 @ 9" o/c	8"	#4 @ 9" o/c
6' 0"	4' 5"	1' 10"	1' 0"	#4 @ 9" o/c	#4 @ 9" o/c	8"	#4 @ 9" o/c

Notes: All concrete shall be Class "A" Concrete with a minimum strength of 3,500 psi.

Reinforcing steel to conform to ASTM A 615, Grade 60

Construction joints will be provided at a maximum spacing of 30 feet.

Minimum splice length for #4 bars = 20 inches

Provide Min. 3 inches of Cover for the reinforcing steel

RETAINING WALL DETAIL

PROJECT NO.
2022-025

SCALE

FIGURE NO.

1

**AG
& E**

Lot 39, Travelers Ridge
Nashville, Tennessee

Use menu item Settings > Printing & Title Block
to set these five lines of information
for your program.

Project Name/Number : lot 39 travel

Title **4 Ft Wall with 3:1 Backslope**

Dsgnr:

Description....

Page : 1
Date: 14 SEP 2022

This Wall in File: c:\users\bobst\documents\retainpro project files\lot 39 travelers ridge.rpx

RetainPro (c) 1987-2019, Build 11.20.03.31

License : KW-06061779


License To : American Geotechnical & Environmental, Inc.

Cantilevered Retaining Wall

Code: IBC 2012,ACI 318-11,ACI 530-11

Criteria

Retained Height	=	6.00 ft
Wall height above soil	=	0.50 ft
Slope Behind Wall	=	3.00
Height of Soil over Toe	=	24.00 in
Water height over heel	=	0.0 ft



Load Factors

Building Code	IBC 2012,ACI
Dead Load	1.200
Live Load	1.600
Earth, H	1.600
Wind, W	1.000
Seismic, E	1.000

Soil Data and Lateral Earth Pressure

Allow Soil Bearing	=	3,000.0 psf	Soil Density, Heel	=	120.00 pcf
Equivalent Fluid Pressure Method			Soil Density, Toe	=	120.00 pcf
Active Heel Pressure	=	32.0 psf/ft	Footing Soil Friction	=	0.400
	=		Soil height to ignore for passive pressure	=	12.00 in
Passive Pressure	=	250.0 psf/ft			

Surcharge Loads

Surcharge Over Heel	=	0.0 psf	Surcharge Over Toe	=	0.0
Used To Resist Sliding & Overturning			Used for Sliding & Overturning		

Axial Load Applied to Stem

Axial Dead Load	=	0.0 lbs	Axial Load Eccentricity	=	0.0 in
Axial Live Load	=	0.0 lbs			

Lateral Load Applied to Stem

Lateral Load	=	0.0 #/ft
...Height to Top	=	0.00 ft
...Height to Bottom	=	0.00 ft
Load Type	=	Wind (W) (Service Level)

Wind on Exposed Stem

Wind on Exposed Stem (Service Level)	=	0.0 psf
---	---	---------

Adjacent Footing Load

Adjacent Footing Load	=	0.0 lbs	Footing Type		Line Load
Footing Width	=	0.00 ft	Base Above/Below Soil		
Eccentricity	=	0.00 in	at Back of Wall	=	0.0 ft
Wall to Ftg CL Dist	=	0.00 ft	Poisson's Ratio	=	0.300

Use menu item Settings > Printing & Title Block
to set these five lines of information
for your program.

Project Name/Number : lot 39 travel
Title 4 Ft Wall with 3:1 Backslope
Dsgnr:
Description....

Page : 2
Date: 14 SEP 2022

This Wall in File: c:\users\bobst\documents\retainpro project files\lot 39 travelers ridge.rpx

RetainPro (c) 1987-2019, Build 11.20.03.31
License : KW-06061779
License To : American Geotechnical & Environmental, Inc.

Cantilevered Retaining Wall

Code: IBC 2012,ACI 318-11,ACI 530-11

Wall Design Summary

Stability Ratios

Overturning = 2.42 OK
Sliding = 2.26 OK

Soil Bearing

Total Bearing Load = 2,543 lbs
...resultant ecc. = 6.49 in

Soil Pressure @ Toe = 1,451 psf OK
Soil Pressure @ Heel = 37 psf OK
Allowable = 3,000 psf
Soil Pressure Less Than Allowable

ACI Factored @ Toe = 2,031 psf
ACI Factored @ Heel = 52 psf

Footing Shear @ Toe = 7.9 psi OK
Footing Shear @ Heel = 7.6 psi OK
Allowable = 82.2 psi

Sliding

Resisting Forces

Sliding Forces

Vertical Forces

Force

Lateral Forces

Force

Soil Over Heel (above water table, if any)	1,020.0 lbs	Heel Active Pressure (above water table, if any)	893.3 lbs
Soil Over Heel (below water table, if any)	0.0	Heel Active Pressure (below water table, if any)	0.0
Water Over Heel	0.0	Hydrostatic Force	0.0
Buoyant Force	0.0	* Heel Active Pressure	893.3
Sloped Soil Over Heel	40.1	Surcharge over Heel	0.0
Surcharge Over Heel	0.0	Adjacent Footing	0.0
Adjacent Footing Load	0.0	Surcharge Over Toe	0.0
Axial Dead Load on Stem	0.0	Load @ Stem Above Soil	0.0
Axial Live Load on Stem *	Omit	Added Lateral Load	0.0
Soil Over Toe	320.0	Seismic Load	0.0
Surcharge Over Toe	0.0	Seismic-Self-weight	0.0
Stem Weight(s)	650.0	Lateral on Key	0.0
Earth @ Stem Transitions	0.0		
Footing Weight	512.5	Totals =	893.3 lbs
Key Weight	0.0		
Vert. Component **	0.0	*Includes water table effect	

Total Vertical Loads

2,542.6 lbs

* Axial live load NOT included in total displayed , or used for overturning
or sliding resistance, but is included for soil pressure calculations.

Sliding Calcs

Lateral Sliding Force = 893.3 lbs
less 100% Passive Force = - 1,000.0 lbs
less 100% Friction Force = - 1,017.1 lbs
Added Force Req'd = 0.0 lbs OK
....for 1.5 Stability = 0.0 lbs OK

Vertical component of active lateral soil pressure IS NOT considered in
the calculation of soil bearing pressures.

Use menu item Settings > Printing & Title Block
to set these five lines of information
for your program.

Project Name/Number : lot 39 travel

Title 4 Ft Wall with 3:1 Backslope

Dsgnr:

Description....

Page : 3
Date: 14 SEP 2022

This Wall in File: c:\users\bobst\documents\retainpro project files\lot 39 travelers ridge.rpx

RetainPro (c) 1987-2019, Build 11.20.03.31

License : KW-06061779

License To : American Geotechnical & Environmental, Inc.

Cantilevered Retaining Wall

Code: IBC 2012,ACI 318-11,ACI 530-11

Overturning

Resisting Moments

<u>Resisting Moments</u>	<u>Force</u>	<u>Distance</u>	<u>Moment</u>
Soil Over Heel (above water table, if any)	1,020.0 lbs	2.71 ft	2,762.5ft-#
Soil Over Heel (below water table, if any)	0.0		
Water Table	0.0		
Soil Over Heel	1,020.0	2.71	2,762.5
Sloped Soil Over Heel	40.1	2.94	118.2
Surcharge Over Heel	0.0		
Adjacent Footing Load	0.0		
Axial Dead Load on Stem	0.0		
Axial Live Load on Stem *	0.0		
Soil Over Toe	320.0	0.67	213.3
Surcharge Over Toe	0.0		
Stem Weight(s)	650.0	1.67	1,083.3
Earth @ Stem Transitions	0.0		
Footing Weight	512.5	1.71	875.5
Key Weight	0.0	1.33	
Vert. Component	0.0		
Total Vertical Loads	2,542.6 lbs		

Resisting Moment 5,052.9 ft-#

Eccentricity -6.5 in

* Axial live load NOT included in total displayed, or used for overturning or sliding resistance, but is included for soil pressure calculations.

Overturning

Overturning Moments

<u>Overturning Moments</u>	<u>Force</u>	<u>Distance</u>	<u>Moment</u>
Heel Active Pressure (above water table, if any)	893.3 lbs	2.33 ft	2,225.1 ft-#
Heel Active Pressure (below water table, if any)	0.0		
Hydrostatic Force	0.0		
Buoyant Force	0.0		
Surcharge over Heel	0.0		
Adjacent Footing	0.0		
Surcharge Over Toe	0.0		
Load @ Stem Above Soil	0.0		
Added Lateral Load	0.0		
Seismic Load	0.0		
Seismic-Self-weight	0.0		
Totals =	893.3 lbs		
Overturning Moment			<u>2,084.5 ft-#</u>

Use menu item Settings > Printing & Title Block
to set these five lines of information
for your program.

Project Name/Number : lot 39 travel
Title 4 Ft Wall with 3:1 Backslope
Dsgnr:
Description....

Page : 4
Date: 14 SEP 2022

This Wall in File: c:\users\bobst\documents\retainpro project files\lot 39 travelers ridge.rpx

RetainPro (c) 1987-2019, Build 11.20.03.31
License : KW-06061779
License To : American Geotechnical & Environmental, Inc.

Cantilevered Retaining Wall

Code: IBC 2012,ACI 318-11,ACI 530-11

Stem Design Summary

		Bottom
		Stem OK
Design Height Above Ftg	ft =	0.00
Wall Material Above "Ht"	=	Concrete
Design Method	=	LRFD
Thickness	=	8.00
Rebar Size	=	# 4
Rebar Spacing	=	9.00
Rebar Placed at	=	Edge
Design Data		
fb/FB + fa/Fa	=	0.258
Total Force @ Section		
Service Level	lbs =	
Strength Level	lbs =	921.6
Moment....Actual		
Service Level	ft-# =	
Strength Level	ft-# =	1,843.2
Moment.....Allowable	=	7,122.4
Shear.....Actual		
Service Level	psi =	
Strength Level	psi =	12.3
Shear.....Allowable	psi =	75.0
Anet	in ² =	
Rebar Depth 'd'	in =	6.25
Masonry Data		
f'm	psi =	
Fs	psi =	
Solid Grouting	=	
Modular Ratio 'n'	=	
Wall Weight	psf =	100.0
Short Term Factor	=	
Equiv. Solid Thick.	=	
Masonry Block Type	=	Medium Weight
Masonry Design Method	=	ASD
Concrete Data		
f'c	psi =	2,500.0
Fy	psi =	60,000.0

Use menu item Settings > Printing & Title Block
to set these five lines of information
for your program.

Project Name/Number : lot 39 travel
Title 4 Ft Wall with 3:1 Backslope
Dsgnr:
Description....

Page : 5
Date: 14 SEP 2022

This Wall in File: c:\users\bobst\documents\retainpro project files\lot 39 travelers ridge.rpx

RetainPro (c) 1987-2019, Build 11.20.03.31
License : KW-06061779
License To : American Geotechnical & Environmental, Inc.

Cantilevered Retaining Wall

Code: IBC 2012,ACI 318-11,ACI 530-11

Concrete Stem Rebar Area Details

Bottom Stem	Vertical Reinforcing	Horizontal Reinforcing	
As (based on applied moment) :	0.0691 in ² /ft		
(4/3) * As :	0.0921 in ² /ft	Min Stem T&S Reinf Area 1.248 in ²	
200bd/fy : 200(12)(6.25)/60000 :	0.25 in ² /ft	Min Stem T&S Reinf Area per ft of stem Height : 0.192 in ² /ft	
0.0018bh : 0.0018(12)(8) :	0.1728 in ² /ft	Horizontal Reinforcing Options :	
	=====	One layer of :	Two layers of :
Required Area :	0.1728 in ² /ft	#4@ 12.50 in	#4@ 25.00 in
Provided Area :	0.2667 in ² /ft	#5@ 19.38 in	#5@ 38.75 in
Maximum Area :	0.8467 in ² /ft	#6@ 27.50 in	#6@ 55.00 in

Footing Data

Toe Width	=	1.33 ft	f'c	=	3,000 psi
Heel Width	=	2.08	Fy	=	60,000 psi
Total Footing Width	=	3.42 ft	Footing Concrete Density	=	150.00 pcf
Footing Thickness	=	12.00 in	Min. As %	=	0.0018
Key Width	=	0.00 in	Rebar Cover @ Top	=	2.00 in
Key Depth	=	0.00 in	@ Bottom	=	3.00 in
Key Distance from Toe	=	1.33 ft			

Footing Design Results

		<u>Toe</u>	<u>Heel</u>
Factored Pressure	=	2,031	52 psf
Mu' : Upward	=	18,923	327 ft-#
Mu' : Downward	=	4,992	1,093 ft-#
Mu: Design	=	1,161	-48 ft-#
Actual 1-Way Shear	=	7.88	7.65 psi
Allow 1-Way Shear	=	82.16	82.16 psi
Toe Reinforcing	=	# 4 @ 9.00 in	
Heel Reinforcing	=	# 4 @ 9.00 in	
Key Reinforcing	=	None Spec'd	

Other Acceptable Sizes & Spacings

Toe: #4@ 9.25 in, #5@ 14.35 in, #6@ 20.37 in, #7@ 27.77 in, #8@ 36.57 in, #9@ 46

Heel: #4@ 9.25 in, #5@ 14.35 in, #6@ 20.37 in, #7@ 27.77 in, #8@ 36.57 in, #9@ 46

Key: No key defined

Min footing T&S reinf Area	0.89 in ²
Min footing T&S reinf Area per fc	0.26 in ² /ft

If one layer of horizontal bars:	If two layers of horizontal bars:
#4@ 9.26 in	#4@ 18.52 in
#5@ 14.35 in	#5@ 28.70 in
#6@ 20.37 in	#6@ 40.74 in

Footing Torsion, Tu	=	0.00 ft-lbs
Footing Allow. Torsion, phi Tu	=	0.00 ft-lbs

If torsion exceeds allowable, provide supplemental design for footing torsion.

Use menu item Settings > Printing & Title Block
to set these five lines of information
for your program.

Project Name/Number : lot 39 travel
Title 4 Ft Wall with 3:1 Backslope
Dsgnr:
Description....

Page : 6
Date: 14 SEP 2022

This Wall in File: c:\users\bobst\documents\retainpro project files\lot 39 travelers ridge.rpx

RetainPro (c) 1987-2019, Build 11.20.03.31
License : KW-06061779

Cantilevered Retaining Wall

Code: IBC 2012,ACI 318-11,ACI 530-11

License To : American Geotechnical & Environmental, Inc.

Tilt

Horizontal Deflection at Top of Wall due to settlement of soil

(Deflection due to wall bending not considered)

Soil Spring Reaction Modulus 250.0 pci

Horizontal Defl @ Top of Wall (approximate only) 0.077 in

The above calculation is not valid if the heel soil bearing pressure exceeds that of the toe.
because the wall would then tend to rotate into the retained soil.

Use menu item Settings > Printing & Title Block
to set these five lines of information
for your program.

Project Name/Number : lot 39 travel

Title **6 Ft Wall with 3:1 Backslope**

Dsgnr:

Description....

Page : 1
Date: 14 SEP 2022

This Wall in File: c:\users\bobst\documents\retainpro project files\lot 39 travelers ridge.rpx

RetainPro (c) 1987-2019, Build 11.20.03.31

License : KW-06061779


License To : American Geotechnical & Environmental, Inc.

Cantilevered Retaining Wall

Code: IBC 2012,ACI 318-11,ACI 530-11

Criteria

Retained Height	=	8.00 ft
Wall height above soil	=	0.50 ft
Slope Behind Wall	=	3.00
Height of Soil over Toe	=	24.00 in
Water height over heel	=	0.0 ft



Load Factors

Building Code	IBC 2012,ACI
Dead Load	1.200
Live Load	1.600
Earth, H	1.600
Wind, W	1.000
Seismic, E	1.000

Soil Data and Lateral Earth Pressure

Allow Soil Bearing	=	3,000.0 psf	Soil Density, Heel	=	120.00 pcf
Equivalent Fluid Pressure Method			Soil Density, Toe	=	120.00 pcf
Active Heel Pressure	=	32.0 psf/ft	Footing Soil Friction	=	0.400
	=		Soil height to ignore for passive pressure	=	12.00 in
Passive Pressure	=	250.0 psf/ft			

Surcharge Loads

Surcharge Over Heel	=	0.0 psf	Surcharge Over Toe	=	0.0
Used To Resist Sliding & Overturning			Used for Sliding & Overturning		

Axial Load Applied to Stem

Axial Dead Load	=	0.0 lbs	Axial Load Eccentricity	=	0.0 in
Axial Live Load	=	0.0 lbs			

Lateral Load Applied to Stem

Lateral Load	=	0.0 #/ft
...Height to Top	=	0.00 ft
...Height to Bottom	=	0.00 ft
Load Type	=	Wind (W) (Service Level)

Wind on Exposed Stem

Wind on Exposed Stem (Service Level)	=	0.0 psf
---	---	---------

Adjacent Footing Load

Adjacent Footing Load	=	0.0 lbs	Footing Type		Line Load
Footing Width	=	0.00 ft	Base Above/Below Soil		
Eccentricity	=	0.00 in	at Back of Wall	=	0.0 ft
Wall to Ftg CL Dist	=	0.00 ft	Poisson's Ratio	=	0.300

Use menu item Settings > Printing & Title Block
to set these five lines of information
for your program.

Project Name/Number : lot 39 travel
Title 6 Ft Wall with 3:1 Backslope
Dsgnr:
Description....

Page : 2
Date: 14 SEP 2022

This Wall in File: c:\users\bobst\documents\retainpro project files\lot 39 travelers ridge.rpx

RetainPro (c) 1987-2019, Build 11.20.03.31
License : KW-06061779
License To : American Geotechnical & Environmental, Inc.

Cantilevered Retaining Wall

Code: IBC 2012,ACI 318-11,ACI 530-11

Wall Design Summary

Stability Ratios

Overturning = 2.32 OK
Sliding = 1.71 OK

Soil Bearing

Total Bearing Load = 3,866 lbs
...resultant ecc. = 8.22 in

Soil Pressure @ Toe = 1,690 psf OK
Soil Pressure @ Heel = 61 psf OK
Allowable = 3,000 psf
Soil Pressure Less Than Allowable

ACI Factored @ Toe = 2,366 psf
ACI Factored @ Heel = 85 psf

Footing Shear @ Toe = 16.7 psi OK
Footing Shear @ Heel = 13.4 psi OK
Allowable = 82.2 psi

Sliding

Resisting Forces

Sliding Forces

Vertical Forces

Force

Lateral Forces

Force

Soil Over Heel (above water table, if any)	1,840.0 lbs	Heel Active Pressure (above water table, if any)	1,486.5 lbs
Soil Over Heel (below water table, if any)	0.0	Heel Active Pressure (below water table, if any)	0.0
Water Over Heel	0.0	Hydrostatic Force	0.0
Buoyant Force	0.0	* Heel Active Pressure	1,486.5
Sloped Soil Over Heel	73.5	Surcharge over Heel	0.0
Surcharge Over Heel	0.0	Adjacent Footing	0.0
Adjacent Footing Load	0.0	Surcharge Over Toe	0.0
Axial Dead Load on Stem	0.0	Load @ Stem Above Soil	0.0
Axial Live Load on Stem *	Omit	Added Lateral Load	0.0
Soil Over Toe	440.0	Seismic Load	0.0
Surcharge Over Toe	0.0	Seismic-Self-weight	0.0
Stem Weight(s)	850.0	Lateral on Key	0.0
Earth @ Stem Transitions	0.0		
Footing Weight	662.5	Totals =	1,486.5 lbs
Key Weight	0.0		
Vert. Component **	0.0	*Includes water table effect	

Total Vertical Loads

3,866.0 lbs

* Axial live load NOT included in total displayed , or used for overturning
or sliding resistance, but is included for soil pressure calculations.

Sliding Calcs

Lateral Sliding Force = 1,486.5 lbs
less 100% Passive Force = - 1,000.0 lbs
less 100% Friction Force = - 1,546.4 lbs
Added Force Req'd = 0.0 lbs OK
....for 1.5 Stability = 0.0 lbs OK

Vertical component of active lateral soil pressure IS NOT considered in
the calculation of soil bearing pressures.

Use menu item Settings > Printing & Title Block
to set these five lines of information
for your program.

Project Name/Number : lot 39 travel

Title 6 Ft Wall with 3:1 Backslope

Dsgnr:

Description....

Page : 3
Date: 14 SEP 2022

This Wall in File: c:\users\bobst\documents\retainpro project files\lot 39 travelers ridge.rpx

RetainPro (c) 1987-2019, Build 11.20.03.31

License : KW-06061779

License To : American Geotechnical & Environmental, Inc.

Cantilevered Retaining Wall

Code: IBC 2012,ACI 318-11,ACI 530-11

Overturning

Resisting Moments

<u>Resisting Moments</u>	<u>Force</u>	<u>Distance</u>	<u>Moment</u>
Soil Over Heel (above water table, if any)	1,840.0 lbs	3.46 ft	6,363.3ft-#
Soil Over Heel (below water table, if any)	0.0		
Water Table	0.0		
Soil Over Heel	1,840.0	3.46	6,363.3
Sloped Soil Over Heel	73.5	3.78	277.6
Surcharge Over Heel	0.0		
Adjacent Footing Load	0.0		
Axial Dead Load on Stem	0.0		
Axial Live Load on Stem *	0.0		
Soil Over Toe	440.0	0.92	403.3
Surcharge Over Toe	0.0		
Stem Weight(s)	850.0	2.17	1,841.7
Earth @ Stem Transitions	0.0		
Footing Weight	662.5	2.21	1,463.0
Key Weight	0.0	1.83	
Vert. Component	0.0		
Total Vertical Loads	3,866.0 lbs		

Resisting Moment 10,348.9 ft-#

Eccentricity **-8.2 in**

* Axial live load NOT included in total displayed, or used for overturning or sliding resistance, but is included for soil pressure calculations.

Overturning

Overturning Moments

<u>Overturning Moments</u>	<u>Force</u>	<u>Distance</u>	<u>Moment</u>
Heel Active Pressure (above water table, if any)	1,486.5 lbs	3.00 ft	4,776.2 ft-#
Heel Active Pressure (below water table, if any)	0.0		
Hydrostatic Force	0.0		
Buoyant Force	0.0		
Surcharge over Heel	0.0		
Adjacent Footing	0.0		
Surcharge Over Toe	0.0		
Load @ Stem Above Soil	0.0		
Added Lateral Load	0.0		
Seismic Load	0.0		
Seismic-Self-weight	0.0		
Totals =	1,486.5 lbs		
Overturning Moment			4,459.6 ft-#

Use menu item Settings > Printing & Title Block
to set these five lines of information
for your program.

Project Name/Number : lot 39 travel

Title 6 Ft Wall with 3:1 Backslope

Dsgnr:
Description....

Page : 4
Date: 14 SEP 2022

This Wall in File: c:\users\bobst\documents\retainpro project files\lot 39 travelers ridge.rpx

RetainPro (c) 1987-2019, Build 11.20.03.31

License : KW-06061779

License To : American Geotechnical & Environmental, Inc.

Cantilevered Retaining Wall

Code: IBC 2012,ACI 318-11,ACI 530-11

Stem Design Summary

		Bottom
		Stem OK
Design Height Above Ftg	ft =	0.00
Wall Material Above "Ht"	=	Concrete
Design Method	=	LRFD
Thickness	=	8.00
Rebar Size	=	# 4
Rebar Spacing	=	9.00
Rebar Placed at	=	Edge
Design Data		
fb/FB + fa/Fa	=	0.613
Total Force @ Section		
Service Level	lbs =	
Strength Level	lbs =	1,638.4
Moment....Actual		
Service Level	ft-# =	
Strength Level	ft-# =	4,369.1
Moment.....Allowable	=	7,122.4
Shear.....Actual		
Service Level	psi =	
Strength Level	psi =	21.8
Shear.....Allowable	psi =	75.0
Anet	in ² =	
Rebar Depth 'd'	in =	6.25
Masonry Data		
f'm	psi =	
Fs	psi =	
Solid Grouting	=	
Modular Ratio 'n'	=	
Wall Weight	psf =	100.0
Short Term Factor	=	
Equiv. Solid Thick.	=	
Masonry Block Type	=	Medium Weight
Masonry Design Method	=	ASD
Concrete Data		
f'c	psi =	2,500.0
Fy	psi =	60,000.0

Use menu item Settings > Printing & Title Block
to set these five lines of information
for your program.

Project Name/Number : lot 39 travel

Title 6 Ft Wall with 3:1 Backslope

Dsgnr:
Description....

Page : 5
Date: 14 SEP 2022

This Wall in File: c:\users\bobst\documents\retainpro project files\lot 39 travelers ridge.rpx

RetainPro (c) 1987-2019, Build 11.20.03.31

License : KW-06061779

License To : American Geotechnical & Environmental, Inc.

Cantilevered Retaining Wall

Code: IBC 2012,ACI 318-11,ACI 530-11

Concrete Stem Rebar Area Details

Bottom Stem	Vertical Reinforcing	Horizontal Reinforcing	
As (based on applied moment) :	0.1637 in ² /ft		
(4/3) * As :	0.2183 in ² /ft	Min Stem T&S Reinf Area 1.632 in ²	
200bd/fy : 200(12)(6.25)/60000 :	0.25 in ² /ft	Min Stem T&S Reinf Area per ft of stem Height : 0.192 in ² /ft	
0.0018bh : 0.0018(12)(8) :	0.1728 in ² /ft	Horizontal Reinforcing Options :	
	=====	One layer of :	Two layers of :
Required Area :	0.2183 in ² /ft	#4@ 12.50 in	#4@ 25.00 in
Provided Area :	0.2667 in ² /ft	#5@ 19.38 in	#5@ 38.75 in
Maximum Area :	0.8467 in ² /ft	#6@ 27.50 in	#6@ 55.00 in

Footing Data

Toe Width	=	1.83 ft	f'c	=	3,000 psi
Heel Width	=	2.58	Fy	=	60,000 psi
Total Footing Width	=	4.42 ft	Footing Concrete Density	=	150.00 pcf
Footing Thickness	=	12.00 in	Min. As %	=	0.0018
Key Width	=	0.00 in	Rebar Cover @ Top	=	2.00 in
Key Depth	=	0.00 in	@ Bottom	=	3.00 in
Key Distance from Toe	=	1.83 ft			

Footing Design Results

		<u>Toe</u>	<u>Heel</u>
Factored Pressure	=	2,366	85 psf
Mu' : Upward	=	41,345	762 ft-#
Mu' : Downward	=	9,438	2,559 ft-#
Mu: Design	=	2,659	-308 ft-#
Actual 1-Way Shear	=	16.67	13.42 psi
Allow 1-Way Shear	=	82.16	82.16 psi
Toe Reinforcing	=	# 4 @ 9.00 in	
Heel Reinforcing	=	# 4 @ 9.00 in	
Key Reinforcing	=	None Spec'd	

Other Acceptable Sizes & Spacings

Toe: #4@ 9.25 in, #5@ 14.35 in, #6@ 20.37 in, #7@ 27.77 in, #8@ 36.57 in, #9@ 46

Heel: #4@ 9.25 in, #5@ 14.35 in, #6@ 20.37 in, #7@ 27.77 in, #8@ 36.57 in, #9@ 46

Key: No key defined

Min footing T&S reinf Area	1.14 in ²
Min footing T&S reinf Area per fc	0.26 in ² /ft

If one layer of horizontal bars:	If two layers of horizontal bars:
#4@ 9.26 in	#4@ 18.52 in
#5@ 14.35 in	#5@ 28.70 in
#6@ 20.37 in	#6@ 40.74 in

Footing Torsion, Tu	=	0.00 ft-lbs
Footing Allow. Torsion, phi Tu	=	0.00 ft-lbs

If torsion exceeds allowable, provide supplemental design for footing torsion.

Use menu item Settings > Printing & Title Block
to set these five lines of information
for your program.

Project Name/Number : lot 39 travel
Title 6 Ft Wall with 3:1 Backslope
Dsgnr:
Description....

Page : 6
Date: 14 SEP 2022

This Wall in File: c:\users\bobst\documents\retainpro project files\lot 39 travelers ridge.rpx

RetainPro (c) 1987-2019, Build 11.20.03.31
License : KW-06061779

Cantilevered Retaining Wall

Code: IBC 2012,ACI 318-11,ACI 530-11

License To : American Geotechnical & Environmental, Inc.

Tilt

Horizontal Deflection at Top of Wall due to settlement of soil

(Deflection due to wall bending not considered)

Soil Spring Reaction Modulus 250.0 pci

Horizontal Defl @ Top of Wall (approximate only) 0.090 in

The above calculation is not valid if the heel soil bearing pressure exceeds that of the toe.
because the wall would then tend to rotate into the retained soil.

MEMORANDUM

To: Mr. Stephen Snow
From: Zac Dufour, P.E.
Kimley-Horn and Associates, Inc.
Date: September 14, 2022
Subject: PC Case 22-27, 1167 Travelers Ridge

We have completed our review of the revised Steep Slope site plan for the proposed new home located at 1167 Travelers Ridge. Please see below for engineering comments.

Comments

1. Removing trees greater than 8" in the front yard will require BZA approval.
 - a. Variance will be needed for removal of trees within the front yard. **VARIANCE APPL. SUBMITTED**
2. Update Sheet 2 to show proper bulk standards. See markup.
 - a. Revised. ✓
3. Provide tree survey of all trees 3" in diameter and greater.
 - a. Provided. ✓
4. Verify front setback based on average of 4 closest lots.
 - a. Verified and provided. ✓
5. Rear setback is 60'.
 - a. Revised. ✓
6. Bold numbers in center of lot on Sheet 3 are not correct. Update to current bulk standards.
 - a. Revised. ✓
7. Remove plat reference to setback lines.
 - a. Removed. ✓
8. Driveway must be 5' off of property line. Add dimensions.
 - a. Dimensions provided. ✓
9. Provide street cut areas around utility connections for sanitary and water, reference metro street cut detail on plans.
 - a. **Provided and noted. Show sawcut area and limits of disturbance for water line connection. PROVIDED, SEE SHEET 4**
10. Provide more spot grades in driveway and around outside of house.
 - a. **Outstanding comment. Need more spot grades around the house and driveway. PROVIDED SHEET 4**
11. Label proposed contours.
 - a. Provided. ✓
12. Provide more grades on wall in rear of house.
 - a. Provided. ✓
13. Retaining wall engineering drawings and calculations are required for walls over 4' in height.
 - a. **Wall drawings have been provided. Structural calculations must be provided as well. TO BE PROVIDED BY OWNER**
14. Provide proposed grading in front of house to match architectural plans – there appears to be about a 20' difference between existing grade and FFE.

FRONT RIGHT CORNER OF HOUSE EXIST. & PROPOSED GRADE IS 778.00. MAIN FLOOR FFE IS 791.30. DIFFERENCE IS 13.30 FEET. THIS THE GROUND LINE SHOWN ON THE ARCH. PLANS IS ~~NOT~~ SLIGHTLY OFF.

- a. Architectural plans have been provided. Additional proposed ground grades will help understand the amount of exposed foundation around the exterior of the house. **THE EXPOSED FOUNDATION IS 13.3 FEET MAXIMUM.**
- 15. Show cleanouts on the MFD.
 - a. MFD has been replaced with a rain garden. Show cleanouts or structures along the 6" pipe run leading to the rain garden. **DONE ✓**
- 16. Is the pipe in the patio intended to be a trench drain? If so label and provide a detail. Need to make sure this water is captured and routed to the MFD.
 - a. This appears to just be a pipe to connect downspout to rain garden. **YES ✓**
- 17. MFD is sized for 5275 but the added impervious area is 7995. MFD must be oversized to account for impervious bypass.
 - a. Rain Garden is sized for full impervious area. **✓**
- 18. Is there a way to grade the driveway and maybe install trench drains to capture more of the driveway area and route it to the MFD?
 - a. Show drainage area to rain garden. Is some of the driveway going towards the rain garden. Rain garden must be sized for the drainage area not just for the added impervious area. **DONE ✓**
- 19. Add a trench drain at the bottom of the driveway to capture water and route to ditch. Add detail for the trench drain.
 - a. This has not been added. 2% cross slope is less than the longitudinal slope of the driveway so not all of the runoff will sheet flow into the roadside ditch. **TRENCH DRAW ADDED. ✓**
- 20. Provide outlet protection for the daylight end of the MFD pipe.
 - a. Show outlet protection for rain garden. How will rain garden outlet – must provide underdrains and show outlet for underdrains. **DONE ✓**
 - b. Provide site specific detail for the rain garden with elevations of each layer and materials. **DONE ✓**
- 21. Show downspout locations and routing to MFDs.
 - a. **Provided. ✓**
- 22. Note trees that are to be removed on the plans.
 - a. **Provided. ✓**
- 23. Tabulate the trees that are to be removed in a table and provide the total caliper inches that are to be removed.
 - a. **Provided. ✓**
- 24. Need to draw in the drip line of all trees. Any proposed improvements or grading that gets into these drip lines needs to have the tree removed and be accounted for in the removal.
 - a. **Provided. ✓**
- 25. Need to show tree protection fencing around all trees that are to be saved. Provide detail of tree protection fencing.
 - a. Provided. Show detail for tree protection fence. **DONE ✓**
- 26. Need to provide tree canopy coverage exhibit showing the existing canopy on the lot and the % of lot canopy coverage. Show proposed canopy that is to be removed. Include table from the tree ordinance.
 - a. **Provided. ✓**
- 27. Provide architectural floor plans and elevations.
 - a. **Provided. ✓**
- 28. Provide an elevation exhibit showing conformance to the recently updated building height regulations. Show actual height to top of roof line. Show the calculated dimensions of the Zone 1, Zone 2 and Zone 3 areas on a plan view exhibit. Show Zone 3 on the side elevation.
 - a. **Not provided. PROVIDED ✓**
- 29. Provide Gross Floor Area Ratio on plans.
 - a. **Not provided. PROVIDED ✓**

30. Provide a statement from geotechnical engineer stating that they have reviewed the current site and grading plans and they comply with the geotechnical recommendations.
 - a. Provided. ✓
31. Provide a statement from structural engineer stating that they have reviewed the current site, grading plans and geotechnical report and the structural drawings are consistent with all other plans.
 - a. Provided. ✓
32. Geotechnical engineer shall be on site during construction to observe conditions and report on the conditions with respect to the initial study, boring data, lab testing and provide any updated recommendations based on any deviations. Geotechnical engineer shall provide a certification letter upon completion of construction prior to the issuance of a certification of occupancy. The certification letter shall speak to the construction methods, geotechnical recommendations that were followed during construction, geotechnical engineer observations during construction and any deviations from the original recommendations that were made.
 - a. Noted. ✓
33. Add steep slope geotechnical requirements per the Steep Slope Ordinance Section 14-238. Add note, "Geotechnical Engineer shall be on site during construction to monitor construction. Engineer shall submit a geotechnical certification letter certifying the stability of the slope and the structure to the City of Oak Hill upon completion of construction and prior to the issuance of a certificate of occupancy."
 - a. Provided. ✓
34. Additional comments may be forthcoming from the Geotechnical engineering review.

You must provide a comment response letter for all of the above comments to be considered for the October Planning Commission.

All revised plans, calculations, and any other supporting documentation along with the full comment response letter must be submitted in email by September 20, 2022.

c: File



MEMORANDUM

To: Mr. Stephen Snow

From: Zac Dufour, P.E.
Kimley-Horn and Associates, Inc.

Date: August 30, 2022

Subject: PC Case 22-27, 1167 Travelers Ridge

We have completed our review of the Steep Slope site plan for the proposed new home located at 1167 Travelers Ridge. Please see below for engineering comments.

Comments

1. Removing trees greater than 8" in the front yard will require BZA approval.
2. Update Sheet 2 to show proper bulk standards. See markup.
3. Provide tree survey of all trees 3" in diameter and greater.
4. Verify front setback based on average of 4 closest lots.
5. Rear setback is 60'.
6. Bold numbers in center of lot on Sheet 3 are not correct. Update to current bulk standards.
7. Remove plat reference to setback lines.
8. Driveway must be 5' off of property line. Add dimensions.
9. Provide street cut areas around utility connections for sanitary and water, reference metro street cut detail and provide detail on plans.
10. Provide more spot grades in driveway and around outside of house.
11. Label proposed contours.
12. Provide more grades on wall in rear of house.
13. Retaining wall engineering drawings and calculations are required for walls over 4' in height.
14. Provide proposed grading in front of house to match architectural plans – there appears to be about a 20' difference between existing grade and FFE.
15. Show cleanouts on the MFD.
16. Is the pipe in the patio intended to be a trench drain? If so label and provide a detail. Need to make sure this water is captured and routed to the MFD.
17. MFD is sized for 5275 but the added impervious area is 7995. MFD must be oversized to account for impervious bypass.
18. Is there a way to grade the driveway and maybe install trench drains to capture more of the driveway area and route it to the MFD?
19. Add a trench drain at the bottom of the driveway to capture water and route to ditch. Add detail for the trench drain.
20. Provide outlet protection for the daylight end of the MFD pipe.
21. Show downspout locations and routing to MFDs.
22. Note trees that are to be removed on the plans.
23. Tabulate the trees that are to be removed in a table and provide the total caliper inches that are to be removed.

24. Need to draw in the drip line of all trees. Any proposed improvements or grading that gets into these drip lines needs to have the tree removed and be accounted for in the removal.
25. Need to show tree protection fencing around all trees that are to be saved. Provide detail of tree protection fencing.
26. Need to provide tree canopy coverage exhibit showing the existing canopy on the lot and the % of lot canopy coverage. Show proposed canopy that is to be removed. Include table from the tree ordinance.
27. Provide architectural floor plans and elevations.
28. Provide an elevation exhibit showing conformance to the recently updated building height regulations. Show actual height to top of roof line. Show the calculated dimensions of the Zone 1, Zone 2 and Zone 3 areas on a plan view exhibit. Show Zone 3 on the side elevation.
29. Provide Gross Floor Area Ratio on plans.
30. Provide a statement from geotechnical engineer stating that they have reviewed the current site and grading plans and they comply with the geotechnical recommendations.
31. Provide a statement from structural engineer stating that they have reviewed the current site, grading plans and geotechnical report and the structural drawings are consistent with all other plans.
32. Geotechnical engineer shall be on site during construction to observe conditions and report on the conditions with respect to the initial study, boring data, lab testing and provide any updated recommendations based on any deviations. Geotechnical engineer shall provide a certification letter upon completion of construction prior to the issuance of a certification of occupancy. The certification letter shall speak to the construction methods, geotechnical recommendations that were followed during construction, geotechnical engineer observations during construction and any deviations from the original recommendations that were made.
33. Add steep slope geotechnical requirements per the Steep Slope Ordinance Section 14-238. Add note, "Geotechnical Engineer shall be on site during construction to monitor construction. Engineer shall submit a geotechnical certification letter certifying the stability of the slope and the structure to the City of Oak Hill upon completion of construction and prior to the issuance of a certificate of occupancy."
34. Additional comments may be forthcoming from the Geotechnical engineering review.

Please provide revised plans, calculations, any other supporting documentation and a comment response letter by September 13, 2022 via email.

c: File

GEO-TECHNOLOGY ASSOCIATES, INC.
GEOTECHNICAL AND
ENVIRONMENTAL CONSULTANTS



A Practicing Geoprofessional Business Association Member Firm

October 2, 2022

Mr. Stephen Snow
Code Enforcement Officer
City of Oak Hill

Re: Report of Geotechnical Review Services
Lot 39 – Inns of Granny White Subdivision
1167 Travelers Ridge
Oak Hill, Tennessee

Mr. Snow:

At your request, Geo-Technology Associates, Inc. (GTA) has reviewed geotechnical information provided for the development of 1167 Travelers Ridge. The planned improvement is to include a residential construction and its associated driveway. The purpose of our review is to evaluate the information provided in the geotechnical report as it relates to the geotechnical aspects of design and the appropriate standard of care.

PROJECT UNDERSTANDING

The following information was provided for review :

- Report titled, “Geotechnical Engineering Study, Lot 39, Inns of Granny White Subdivision, City of Oak Hill, Tennessee,” prepared by American Geotechnical and Environmental, Inc. dated May 7, 2022
- Site – Grading Plans prepared by Snyder Engineering, PLLC dated August 30, 2022

The planned improvement will include a one- to two-story, residential structure. Based on the drawings provided, the first level will have a finished floor elevation of 791.3; with a garage level established at 782.0.

According to the site plan, the ground surface elevation across the proposed building areas varies from about elevation 790 within the western limits of the proposed structure to elevation 774 in the eastern limits of the proposed structure.

230 Great Circle Rd, Suite 211 Nashville, TN 37228 (615) 509-6012

◆ Abingdon, MD ◆ Baltimore, MD ◆ Laurel, MD ◆ Frederick, MD ◆ Waldorf, MD ◆ New Castle, DE ◆ Georgetown, DE ◆ Somerset, NJ
◆ NYC Metro ◆ York, PA ◆ Quakertown, PA ◆ Beaver Falls, PA ◆ Malvern, OH ◆ Sterling, VA ◆ Nashville, TN ◆ Charlotte, NC ◆ Raleigh, NC

Visit us on the web at www.gtaeng.com

REVIEW AND CONCLUSIONS

American Geotechnical and Environmental, Inc (AG&E) observed the excavation of five test pits to explore the subsurface conditions at the site. Each of the test pits encountered topsoil underlain by colluvial soils extending to depths of 5.6 feet to 9.0 feet below existing site grades. The colluvial soils consist of two layers. The upper layer is a brown cherty silty clay that is underlain by brown to yellowish brown silty clays that contain some chert fragments and some slickenside faces at depths of 3.7 to 8.2 feet. Slickenside faces are secondary structures in the soil that have been smoothed, or polished, by movement of the soil. The lower stratum of colluvial soil extends to depths of 5.6 to 9.0 feet; beneath the colluvial soil is residual silty clays.

Bedrock was not explored, however, based on the review of the available geologic maps, “*Geologic Map of the Oak Hill Quadrangle, Tennessee*” (Tennessee Division of Geology 1972). The site is underlain by limestone of the Leipers and Catheys Formations, which consist of thin- to medium-bedded shaly limestone.

Due to the presence of the colluvial soils, AG&E performed numerous slope stability analysis to assess the stability of the subgrade as a result of the proposed construction. The slope stability analysis yielded unfavorable results based on standard shallow foundation construction. Accordingly, the analysis we performed based on a revised foundation construction. Specifically, AG&E recommends that the proposed foundation excavations extend to a depth necessary to completely penetrate the colluvial soil and bear at least 2 feet into the underlying residual soils.

Accordingly, the foundation installation may require excavations on the order of 8 feet to 11 feet to completely penetrate the colluvial soils and expose the residual soils.

We recommend that AG&E be on site during foundation excavations to confirm that foundation excavations completely penetrate the colluvial soil and extend at least 2 feet into the underlying residual soil.

In our opinion, the AG&E, Inc.’s geotechnical report fulfills the geotechnical requirements for development.

We trust that this letter meets your immediate needs. If you require additional information, please let us know.

Sincerely,

Geo-Technology Associates, Inc.



Daniel D. Terranova, PE